

DOOR SCHEDULE							
	EXTERNAL	EXTERNAL	EXTERNAL	EXTERNAL	EXTERNAL	INTERNAL	EXTERNAL
DOOR NO.	D1	D2	D3	D4	D5	D6	D7
NO. REQUIRED	1	1	1	2	2	7	1
DOOR	AL. FOLDING STACK GLASS DOOR WITH APPROVED WEATHER SEAL AND STEP	AL. FOLDING STACK GLASS DOOR WITH APPROVED WEATHER SEAL AND STEP	AL. FOLDING STACK GLASS DOOR WITH APPROVED WEATHER SEAL AND STEP	AL. AND GLASS DOOR WITH APPROVED WEATHER SEAL AND STEP	SOLID TIMBER DOOR WITH DETAIL TO CLIENT. PROVIDE APPROVED WEATHER SEAL AND STEP	SOLID TIMBER DOOR WITH DETAIL TO CLIENT.	AL. SLIDING GLASS DOOR SD 3621 0XX0
FRAME	AL. THERMAL BREAK FRAME TO MANUFACTURER REBATE: FOLDING STACK	AL. THERMAL BREAK FRAME TO MANUFACTURER REBATE: FOLDING STACK	AL. THERMAL BREAK FRAME TO MANUFACTURER REBATE: FOLDING STACK	AL. THERMAL BREAK FRAME TO MANUFACTURER REBATE: FOLDING STACK	TIMBER FRAME TO MANUFACTURER REBATE: LH = 0 / RH = 2	TIMBER FRAME TO MANUFACTURER REBATE: LH = 3 / RH = 4	AL. THERMAL BREAK FRAME TO MANUFACTURER REBATE: FOLDING STACK
LOCATION	GST: POOL ROOM	GST: BAR	GST: TV ROOM AND DINING ROOM	GST:BEDROOM 1 AND BEDROOM 2	GST: SCULLERY AND WC	GST: SCULLERY AND BATHROOM, EN-SUITE AND BEDROOMS	GST: BAR
GLAZING	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	NONE	NONE	SINGLE CLEAR 6.38mm SAFETY GLASS WITH APPROVED MARKERS


ALL WINDOWS AND DOORS TO BE CHECKED,COUNTED AND OPENINGS MEASURED BEFORE ORDERING

WINDOW SCHEDULE							
	W1	W2	W3	W4	W5	W6	W7
NO. REQUIRED	1	1	1	6	2	2	1
SIZE	4500x2195	4500x2195	4000x2125	900x900	2000x1800	1200x1800	1500x1200
DESCRIPTION	CUSTOM MADE	CUSTOM MADE	FIXED PANE	PT199	PTT2018	PTT1218	PTT1512
LOCATION	GST: BAR ABOVE D2	GST: POOL AREA ABOVE D1	GST: BAR	GST: BATHROOM, WC, GWC AND EN-SUITE SCULLERY	GST: BEDROOM 3 AND BEDROOM 4	GST: BEDROOM 3 AND BEDROOM 4	GST: POOL AREA
GLAZING	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE OBSCURED GLAZING	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS	SINGLE CLEAR 6.38mm LOW E SAFETY GLASS WITH APPROVED MARKERS
NOTES:	AL. THERMAL BREAK FRAMES TO CLIENTS SPECIFICATION						
ADDITIONAL:	OBSCURED GLAZING TO ALL BATHROOM WINDOWS						

ALL WINDOWS AND DOORS TO BE CHECKED,COUNTED AND OPENINGS MEASURED BEFORE ORDERING


TO BE READ IN CONJUNCTION WITH RATIONAL DESIGN

Worst-case whole glazing element performance figures.				
1	2	3	4	5
Glass Description	Performance Values			
	Aluminium / Steel Framing		Timber / uPVC / *Aluminium Framing	
	Total U-value	SHGC	Total U-value	SHGC
Single – clear	7.9	0.81	5.6	0.77
Single – tinted	7.9	0.69	5.6	0.65
Single Low E	5.73	0.66	4.06	0.63
Clear Double (3/6/3)	4.23	0.72	3	0.68
Tinted Double	4.23	0.59	3	0.56
Clear Double Low E	3.4	0.66	2.41	0.62
Tinted Double Low E	3.4	0.54	2.41	0.51
(*) Thermal Break Framing				




TYPICAL LINTEL DETAIL

SCALE 1:20



BOE WINDOW CILL DETAIL

SCALE 1:20



SHADING ELEMENT DETAIL AND CALC

TABLE 5.1.9

MINIMUM NUMBER OF COURSES	MAXIMUM ROOF SPAN		
	NO ROOF	LIGHT ROOF	HEAVY ROOF
85MM COURSE HEIGHT:	NOMINAL THICKNESS ≤ 140mm		
4	3.0	2.0	1.5
5	3.0	2.5	2.0
6	3.0	3.0	2.5
9	3.0	3.0	3.0
85MM COURSE HEIGHT:	NOMINAL THICKNESS < 190mm		
4	3.0	2.0	2.0
5	3.5	2.5	2.5
6	3.5	3.5	3.0
9	3.5	3.5	3.5
100MM COURSE HEIGHT:	NOMINAL THICKNESS < 140mm		
3	3.0	2.0	1.5
4	3.0	2.5	2.0
5	3.0	3.0	2.5
8	3.0	3.0	2.5
100MM COURSE HEIGHT:	NOMINAL THICKNESS < 190mm		
3	2.5	2.0	2.0
4	3.0	2.5	2.0
5	3.5	3.5	3.0
8	3.5	3.5	3.5

PRE-STRESSED CONCRETE LINTELS :

PRECAST CONCRETE LINTELS SHALL COMPLY WITH THE RELEVANT REQUIREMENTS OF SABS 1504 AND BE BUILT INTO WALLS COMPOSITELY WITH MASONRY. SUCH LINTELS SHALL BE CONSTRUCTED IN ACCORDANCE WITH TABLE 5.8 AND CONTAIN NOT LESS THAN THE NUMBER OF COURSES SET OUT IN TABLE 5.2 SECONDARY REINFORCEMENT IN ACCORDANCE WITH TABLE 5.1.5 SHALL BE PROVIDED IN UPPERMOST BED JOINTS. LINTELS SHALL BE SET IN CLASS II MORTAR AND HAVE A MINIMUM BEARING OF:

* LINTELS SUPPORTING MASONRY ONLY =150mm

* LINTELS SUPPORTING ROOF TRUSSES

SPAN <1.5m =150mm

SPAN1.5-2.5m=250mm

SPAN >2.5m =350mm

LINTELS SHALL BE CLEANED AND WETTED PRIOR TO RECEIVING MORTAR

LINTELS THAT SUPPORT ROOF TRUSSES TO BE BUILT INTO BRICKWORK:

1. LINTELS WITH A SPAN OF 1.5m OR LESS = 150MM

2. SPAN OF 1.5M - 2.5M = 250MM

3. SPAN GREATER THAN 2.5M = 350MM

LINTELS TO BE SUPPORTED ADEQUATELY FOR NOT LESS THAN 7 DAYS AFTER COMPLETION

ALL DIMENSIONS TO BE MEASURED OUT AND PEGGED ON SITE BEFORE COMMENCING WORK

ALL REINFORCED CONCRETE SLABS, FOUNDATIONS, COLUMN DETAILS, BEAMS, STAIRS AND RETAINING WALLS TO BE BUILT STRICTLY IN ACCORDANCE WITH ENGINEERS DETAIL AND UNDER HIS/HER SUPERVISION

BUILDING MUST BE IN ACCORDANCE WITH THE APPROVED BUILDING PLAN. NO CHANGES MAY BE MADE TO SUCH PLANS WITHOUT THE EXPRESSED CONSENT OF THE AUTHOR OF SUCH DOCUMENT

FLOORS,WALLS,GEYSER PIPES AND ROOFS TO BE INSULATED IN ACCORDANCE WITH SANS 10400

ARCHITECTURAL DRAWINGS TO BE READ IN CONJUNCTION WITH ENGINEERING DRAWINGS

COPYRIGHT NOTICE

Copyright © 2011 (Open Studio Designs cc). Copyright subsists in this drawing. The person or entity whose name appears in the title block of this drawing, is hereby granted a non-exclusive license to use, display, print and / or reproduce this drawing to the extent necessary to carry out and complete the project described in the title block of this drawing.

This license in respect of the copyright is expressly limited as aforesaid and the person and/or entity referred to above shall not be entitled to grant sub-licenses in respect of the copyright in this drawing to any other entity.

This license confers no ownership rights in the copyright vesting in the drawing and this drawing and the copyright subsisting therein will, at all times, remain the property of (Open Studio Design cc).

Any unauthorized reproduction, publication, transmission, publication, adaptation and/or inclusion of this drawing in a cinematograph film or television broadcast is an act of copyright infringement which will render the doer of the act liable for civil law copyright infringement and may in certain circumstances render the doer liable to criminal prosecution .

Requests and enquiries concerning this drawing and the rights subsisting therein should be addressed to the copyright owner.

ACTS OF PARLIAMENT

All Contractors shall ensure that, before any work is put in hand, they comply with all the necessary Acts of Parliament of the Republic of South Africa.

REQUIREMENTS

1. GENERAL
- 1.1 THIS DRAWING IS NOT TO BE SCALED, USE FIGURED DIMENSIONS ONLY. ALL DIMENSIONS AND HEIGHTS TO BE CHECKED AND VERIFIED BEFORE ANY WORK COMMENCES ON SITE. ANY DISCREPANCIES SHALL BE REPORTED TO THE ARCHITECT IMMEDIATELY. ALL LEVELS, HEIGHTS OF PLINTHS, DEPTH OF EXCAVATIONS AND NUMBER OF STEPS TO BE FINALLY CHECKED BY CONTRACTOR ON SITE.
- 1.2 THE SITE TO BE TREATED IN ACCORDANCE WITH S.A.B.S. CODE OF PRACTICE NO. 0124-1977 WITH SHELLDRITE TERMITEPROOF SOIL POISONER.
- 1.3 TOP OF FOUNDATIONS TO BE A MINIMUM OF 300mm BELOW NATURAL GROUND LEVEL.
- 1.4 BACKFILL TO FOUNDATIONS.
- 1.5 TOP OF 75mm CONCRETE SURFACE BED TO BE MINIMUM OF 150mm ABOVE FINISHED GROUND LEVEL.
- 1.6 75mm THICK CONCRETE SURFACE BED TO BE ON 'GUNPLAS' USB GREEN DAMP PROOF MEMBRANE ON SAND BINDING ON WELL COMPACTED FILL.
- 1.7 'GUNDLE' BRICKGRIP S.A.B.S. EMBOSSED D.P.C 375 MIC. UNDER ALL WALLS, WINDOW CILLS AND AT CHANGES IN FLOOR LEVELS.
- 1.8 STORMWATER SHALL BE REMOVED FROM DWELLING, YARD AND SITE.
- 1.9 ELECTRICAL INSTALLATION SHALL BE 'HEINEMANN' EARTH LEAKAGE SYSTEM IN DISTRIBUTION BOARD.
- 1.10 ALL BUILDING WORK TO BE CARRIED OUT IN ACCORDANCE WITH LOCAL AUTHORITIES BUILDING BY-LAWS AND REGULATIONS.

2. FOUNDATIONS

- 2.1 ALL FOUNDATIONS, RETAINING WALLS, STRUCTURAL CONCRETE WORK AND SUB SOIL STORMWATER DRAINAGE TO CIVIL ENGS SPECIFICATIONS.
- 2.2 ALL SOIL COMPACTION TO CIVIL ENGS SPECIFICATIONS.
- 2.3 ALL FOUNDATIONS TO BE REINFORCED AS REQUIRED BY ENGINEER.

3. FLOORS

- 3.1 MIN. 75mm CONCRETE SURFACE BED.
- 3.2 25mm CEMENT SCREED TO ALL FLOORS.
- 3.3 SKIRTING TO BE PROVIDED.

4. WALLS

- 4.1 220mm BRICK WALLS WITH GUNDLE BRICKGRIP DPC.
- 4.2 BRICKFORCE EVERY 4 COURSES AND EVERY COURSE FOR 4 COURSES OVER OPENINGS
- 4.3 ALL BRICKWORK MIN. 7 mPa CLASS II.
- 4.4 WINDOWS BUILT IN WITH GUNDLE BRICKGRIP DPC.
- 4.5 ALL PAINTWORK TO COMPLY WITH MANUFACTURER'S SPECIFICATIONS WITH NECESSARY UNDERCOATS.
- 4.6 EXTERNAL-TO PLAN INTERNAL-PLASTER AND PAINT.

ALL LEVELS, DIMENSIONS, DEPTHS OF EXCAVATIONS, HEIGHTS OF PLINTHS, NUMBER OF STEPS AND SIZES OF FOUNDATIONS TO BE PLACED AT A HEIGHT OF EXISTING STRUCTURE

5. ROOF A


- 5.1 CONCRETE ROOF TILES @ 26° ON 38x38mm GRADED S.A. PINE TIMBER BATTENS @ 320mm C/C MAX ON 225x38mm PRE-FABRICATED, AS PER ENGINEER, S.A. PINE TRUSSES @ 760mm C/C MAX ON 114x38mm TIMBER WALL PLATES. TRUSSES TO BE ANCHORED WITH TWO STRANDS OF 25mm GALVANIZED STEEL WIRE FIXED 300mm DEEP IN BRICK WALL. PROVIDE SABS APPROVED PLASTIC UNDERLAY AND ISALATION INSULATION.
- 5.2 MIN.170mm CONCRETE SLAB TO ENGINEER'S DETAIL AND DESIGN.
- 5.3 MIN. 55mm VEMICULITE INSULATING SCREED TO 1:60 FALL.
- 5.4 WATERPROOFING BY SPECIALIST TO MANUFACTURERS SPEC.
- 5.5 1500 P.V.C RAINWATER DOWNPIPES FROM FULLBORE OUTLETS.
- 5.6 SKYLIGHTS TO MANUFACTURERS SPEC.
- 5.7 GUTTERS: MARLEY STREAMLINE SQUARE PROFILE RAINWATER GUTTERS + DOWNPIPES.
- 5.8 3mm SKM COAT RHINOLITE ON PLASTERBOARD CEILING FIXED TO 38x 38mm S.A. PINE BRANDEING AT 450mm C/C FIXED TO TIE BEAMS.

6. WINDOWS AND DOORS

- 6.1 ANY PANE OF GLASS WHICH IS TO BE INSTALLED WITHOUT SUPPORT FRAME SHALL BE IN ACCORDANCE WITH SABS 0137
- 6.2 THICKNESS OF PANES IN RELATION TO THEIR AREA SHALL BE IN ACCORDANCE WITH SABS 0137
- 6.3 EXTERNAL SLIDING DOORS: STANDARD AS PER WINDOWS TO SCHEDULE.
- 6.4 INTERNAL DOORS: STANDARD HARDWOOD FRAMES TO SCHEDULE
- 6.5 WINDOWS: TO SCHEDULE
- 6.6 SLIDING DOORS: DOORS TO SCHEDULE.

7. DRAINAGE NOTES

- 7.1 1000 uPVC SEWER PIPE DRAIN WITH A MIN. FALL OF 1:60.
- 7.2 1000 OVP. AT HEAD OF DRAIN PIPE AS SHOWN.
- 7.3 RODDING EYES AT HEAD OF DRAIN, AT ALL CHANGES OF DIRECTION AND AT MAX. OF 25000 INTERVALS.
- 7.4 INSPECTION EYES AT ALL JUNCTIONS OF DRAIN, AND TO HAVE MARKED COVERS AT GROUND LEVEL.
- 7.5 DRAIN PIPE UNDER BUILDINGS TO BE PROTECTED AGAINST LOAD.
- 7.6 ALL WASTE PIPE TO HAVE 65mm RE-SEAL TRAPS, ALL WASTE PIPES TO BE ACCESSIBLE OVER ENTIRE LENGTH FOR CLEANING AND REPAIRS.
- 7.7 ALL WASTE PIPES UNDER FLOOR SLAB TO BE SLEEVED.
- 7.8 ALL SOIL FITTINGS WITH VERTICAL DISCHARGE GREATER THAN 1220 TO HAVE ANTISYPHON VENTPIPES.
- 7.9 RAINWATER DOWNPIPES TO DISCHARGE A MIN. OF 2440 FROM ANY
- 7.10 ALL DRAINAGE WORK TO BE CARRIED OUT IN ACCORDANCE WITH LOCAL AUTHORITIES DRAINAGE BY-LAWS AND REGULATIONS.



Open Studio Designs
Architectural & Interiors

Mobile 083-306-4315
Fax-086-543-8765
openstudio.design@gmail.com

STAND DESCRIPTION
NEW PROPOSED DWELLING ON
PTN 465 OF THE FARM
KROMDRAAI 560KQ
CLIENT:

WORKING DRAWINGS

TECHNOLOGISTS: W JUNG-KRUGER
ARCHITECT: W.R ELLIS

DATE: NOV 18 DWG NO:
DRAWN: WJK SHEET:03 OF 10